

PART 3 EXECUTION

3.1 INSTALLATION

- A. General: Install units in locations shown on plans and in accordance with manufacturer's instructions.
- B. Any floor penetrations are to be thoroughly sealed to ensure the watertightness and integrity of the entire floor.
- C. Install units on a flat surface level within 1/8" and of sufficient strength to support the units.
- D. Provide components furnished as per manufacturer's literature.
- E. Provide all water piping so water circuits are serviceable, without having to dismantle excessive lengths of pipe.
- F. Provide drain valves and vent cocks to each coil.
- G. Provide certified wiring schematics to the electrical division for the equipment and controls.
- H. Provide all necessary control wiring as recommended by the manufacturer.
- I. Provide condensate traps in accordance with manufacturers recommendations. Pipe to nearest floor drain or as indicated on the plans.
- J. Provide extended lubrication line to permit lubrication for bearings to be performed from the access door side of the unit.

3.2 APPROVED MANUFACTURERS

- A. Haakon
- B. Mafna
- C. HuntAir

END OF SECTION