

(C) Ingenia Technologies Inc.

→ (D) Mafna

(E) Scott Springfield

(F) Ventrol

2. fans

(A) Twin City Fan & Blower Co.

(B) Loren Cook

(C) Approved equivalent

3. heat transfer coils

(A) Aerofin Canada Services Inc.

(B) Heatcraft Inc.

(C) McQuay

4. filters

(A) CamfilFarr Inc.

(B) Approved equivalent

PART 3. EXECUTION

3.1 INSTALLATION OF CUSTOM MADE AIR HANDLING UNITS

A. Provide custom made air handling units where shown.

B. Give a minimum of seven (7) working days notice prior to commencement of factory tests and unit inspections specified in Part 2 of this Section. Make all required travel and accommodation arrangements (from Toronto) on behalf of the Consultant, and ensure that travel tickets, itinerary, etc., are in the Consultant's hands well prior to the depart date.